

District Engineer's (Buildings) Office - Hambanthota

REPAIR OF TILES AND ELECTRICAL SYSTEM IN OFFICE BUILDING AT DIVISIONAL SECRETARIAT

OFFICE THISSAMAHARAMA

ID	Description	Unit	Qty.	Rate	Amount
(No Topic Assigned)					
	<u>PRELIMINARY WORKS</u>				
1	Provisional Sum for making cover to prevent dust	PS	1.00	30,000.00	30,000.00
2	Provisional Sum Temporary sheds & sanitary accommodation of workmen	PS	1.00	40,000.00	40,000.00
3	Provisional Sum Employee Full Time Civil technical Officer having qualification such N.C.T With years experience or equivalent	month	3.00	25,000.00	75,000.00
	Total carried to summary				
	<u>DEMOLISH WORKS</u>				
4	Removing Aluminium partitions carefully at all joints for reusing and stacking at site	Sq.m	288.00		
5	Demolishing tiles with tile bed and clearing debris away from site and transport in to a dump pit away from premises, 1st floor	Sq.m	688.00		
6	Demolishing tiles with tile bed and clearing debris away from site and transport in to a dump pit away from premises, -2nd floor	Sq.m	555.00		
7	Removing soffit plaster and clearing debris away from site and transport in to a dump pit away from premises,	Sq.m	22.00		
8	Demolishing reinforced cement concrete in suspended floors, removing reinforcement and clearing debris away from site and transport in to a dump pit away from premises, (for minor works)	Cu.m	0.40		
9	Removing and stacking Aluminium Door or Window with frame from exsisting wall & finish the wall in good condition	Sq.m	5.80		
10	Removing and stacking , Iron grill with frame from wall. and re-fix after renovation.	Sq.m	5.80		
11	Demolishing brickwork in cement clearing debris away from site and transport in to a dump pit away from premises,	Cu.m	0.80		
12	Provisional sum for dismantling extended casing wiring	ps	1.00	20,000.00	20,000.00
	Total carried to summary				
	<u>BRICK WORKS</u>				
13	Brickwork in 225 mm 1:5 cement : sand mortar (First Floor).	Cu.m	1.00		
	Total carried to summary				

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
	<u>CONCRETE WORKS</u>				
14	R.C.C. 1: 1 1/2: 3(3/4") in 4" thick slab in ground floor, using mixer and vibrator. (Reinforcement and shuttering paid separately). (GRADE 25).including curing-sun shade/Balcony	Cu.m	0.40		
	Total carried to summary				
	<u>REINFORCEMENT WORKS</u>				
15	10mm Tor steel Ground floor-Sun shade	Kg	35.00		
	Total carried to summary				
	<u>PAVING WORKS</u>				
16	Preparing surface and applying 01coat of APCOFLOOR -HFP 120 primer, 02coats of APCOFLOOR-TC510 and 02coats of APCOFLOOR-TC600 semi-gloss finish Epoxy floor with 50 to 67.5mm height skirting including forming expansion joint if necessary(05 year warrenty).Rate including repairs with 3:1 cement:polymer modified cement for minor cracks and Epoxy motar filling for any other cracks. making dust free surface before paving application included. NOTE: Application will start after 45days of the order conformation with 50% advance payment.	m2	555.00		
	Total carried to summary				
	<u>PLASTER WORKS</u>				
17	1/2" thk 1:3 Cement Rendering finished smooth with neat cement floating, Ground floor(sand to be sieved with 1/8" nets) Rate to include making dust free surface before rendering & curing- 1st Floor	Sq.m	660.00		
18	Skirting in Cement mortar 1:3, 1/2" X 4" projected to wall finish with floating including forming groove. (1st floor)	m	284.00		
19	3/8 " Thick plastering to RCC beams, slab soffit ,column in cement and sand 1:3 1st floor.	Sq.m	22.00		
20	Provisional sum for sunshade & balcony repair with chemical plaster - GF,1st F & 2nd F	PS	1.00	30,000.00	30,000.00
21	3/8 " Thick plastering to RCC beams, slab soffit , column in cement and sand 1:3 (G: Floor)	Sq.m	5.00		
22	Cement copping in 1:4 Cement , Sand mortar 1" x 3/4 on underside of concrete slab, for prevent the rain Water flowing (Ground floor).(Wahi kenda)	m	10.10		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
23	1/2" thk 1:2 Cement Rendering finished smooth with neat cement floating ; G/F (Water Proofing purpose only) rate to include Curing	Sq.m	4.00		
24	Cement Sand plastering to wall 1:5, (5/8") thick semi rough 1st floor. rate to include curing	Sq.m	6.50		
25	Reveals exceeding 100 mm, but not exceeding 200 mm wide with 1:5 ct : sand mortar 16.0 mm thick finished semi rough.(1st floor).	m	10.00		
	Total carried to summary				
	ELECTRICAL WORKS				
26	Supply and fixing 13Amp socket outlet with necessary PVC casing wiring (7/0.53 PVC single wire 1.5mm2) 1 core ×2, 7/0.53 earth wire (1.5mm2) all complete as per the instruction. (Socket - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Casing - Polycrome/Krypton) (Fittings - Krypton/Polycrome/Orange)	Nr	77.00		
27	Supply and fixing 13Amp socket outlet with necessary PVC wall & floor casing wiring (7/0.53 PVC single wire 1.5mm2) 1 core ×2, 7/0.53 earth wire (1.5mm2) all complete as per the instruction.(Socket - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Casing - Polycrome/Krypton) (Fittings - Krypton/Polycrome/Orange)	Nr	205.00		
28	Supply and fixing 13A socket outlet with necessary PVC casing wiring (7/0.67 PVC single wire 2.5mm2) 1 core ×2, 7/0.67 earth wire (2.5mm2) all complete as per the instruction.(Socket - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Casing - Polycrome/Krypton) (Fittings - Krypton/Polycrome/Orange)	Nr	8.00		
29	Supply and fixing 1Nr ceiling fan point wiring pvc casing including 1/1.13 1mm2 1C×2 wire/ 1/1.13 1mm2 earth wire / gang switch 1 way/ sunk box/and fixing materials all complete as per the instruction (Switch - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (fittings - krypton/Polycrome/Orange) (Casing - krypton/Polycrome)	Nr	10.00		
30	Supply and fixing 56" ceiling fan with fan speed controller including connecting materials (make KDK model N56RG SLS company warrenty certificate) all complete as per the instruction.	Nr	9.00		
31	Supply and fixing 16" sweep wall fan with 13 maxAmp socket outlet ,Necessary concealed conduit wiring (1/1.13 wire 1.0mm2, 1/1.13 earth wire 1mm2) all complete as per instruction. Make KDK with warranty (SLSI Approved makes Model - M40C) fixed to wall with Philips screws (Socket - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Conduit - Polycrome/Krypton) (Fittings - Krypton/Polycrome/Orange)	Nr	1.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
32	Supplying and fixing (7/0.67)(Cu/PVC/PVC) (Twin) P.V.C (Cu) Sub Main Wire (2.5 mm2) [(Cable - ACL Fire Guard/Kelani/Orange/Sierra) Cable SLS 733]	m	46.00		
33	Supplying and fixing 7/0.67 (Cu/PVC) (2.5 mm2) Earth wire. All Complete as per Instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra)	m	46.00		
34	Supply and fixing 1Nr ceiling fan point wiring pvc casing including 1/1.13 1mm2 1C×2 wire/ 1/1.13 1mm2 earth wire / gang switch 1 way/ sunk box/and fixing materials all complete as per the instruction (Switch - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (fittings - krypton/Polycrome/Orange) (Casing - krypton/Polycrome)	Nr	1.00		
35	Supplying and fixing consumer unit 04 way surface mounted M.C.B type (incl.32 Amp. D.P MCB,40 Amp/30 mA-D.P RCCB, 4 nrs M.C.B (6 Amp.-16 Amp.)500 encloser box & bus bar fixing Philips screws (MCB - Make - Orange electric 10kA/ Schneider/Chint EB/NB7/SIMENS 5SL6 Betagard) (RCCB Make - Orange electric 10kA/Schneider/Chint NL1/SIMENS 5SV5) (Enclosure - Polycrome) Original Makes with company warranty Certificate. all complete as per instruction	Nr	2.00		
36	Supplying and fixing consumer unit 08way surface mounted M.C.B type (incl.32 Amp. D.P MCB,40 Amp/30 mA-D.P RCCB, 8 nrs M.C.B (6 Amp.-16 Amp.)900 ABC encloser box & bus bar ,fixing Philips screws (MCB-Make -Orange electric 10kA/ Schneider/Chint NB 7/EB/SIMENS 5SL6 Betagard) (RCCB Make -Orange electric 10kA/Schneider/Chint NL1/SIMENS 5SV5) (Enclosure- Polychrome)Original Makes with company warranty Certificate. all complete as per instruction	Nr	1.00		
37	Supplying & fixing 7/1.70(16mm2) (Cu/PVC/PVC) ,4x 1C ,three phase main wire incl: PVC trunking (50mm X 25mm)all complete as per instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (PVC trunking - Krypton/Polycrome)- Cable SLS 733]	m	10.00		
38	Supplying and fixing 7/1.70 (Cu/PVC)(16- mm2) Earth wire. All Complete as per Instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra)	m	10.00		
39	Supplying and fixing 2" dia galvanized iron earth pipe 6'-0"(1800 mm) long (heavy duty) and connected the7/1.70 earth wire (16mm2) with cable LUG . Including brick chamber with cover slab as per Drawing. (DB to Earth pipe cable / conduit length 8 m) [Cable SLS 733] (Cable - ACL Fire Guard/Kelani/Orange/Sierra)(for 60A three phase supplies only)	Nr	2.00		
40	Supplying & fixing 7/1.04(6mm2)(Cu/PVC/PVC) ,4 x 1C ,three phase main wire & 7/1.04 (6mm2) earth wire incl: PVC Conduit all complete as per instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Conduit - Polycrome/Krypton)- Cable SLS 733	m	117.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
41	Supplying & fixing 7/1.35(Cu/ PVC/PVC)(10mm2) ,4 x 1C ,three phase main wire & 7/1.35 (10mm2) earth wire incl: PVC Conduit all complete as per instruction(Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Conduit - Polycrome/Krypton)	m	10.00		
42	Supplying & fixing 7/1.04(6mm2)(Cu/PVC/PVC) , 1 core x 2 (single phase main wire) & 7/1.04(6mm2) earth wire , incl: PVC conduit all complete as per instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Conduit - Polycrome/Krypton) [Cable SLS 733]	m	90.00		
43	Supplying and fixing consumer unit 10 way surface mounted M.C.B type (incl.32 Amp. D.P MCB,40 Amp/30 mA-D.P RCCB, 10 nrs M.C.B (6 Amp -16 Amp.)900 encloser box & bus bar , fixing Philips screws (MCB-Make - Orange electric 10kA/ Schneider/Chint NB 7/EB/SIMENS 5SL6 Betagard) (RCCB Make - Orange electric 10kA/Schneider/Chint NL1/SIMENS 5SV5) (Enclosure - Polychrome)Original Makes with company warranty Certificate. all complete as per instruction	Nr	1.00		
44	Supplying and fixing 63Amp 3 phase main panel board. Including 1nr 63A 4pole MCCB,1nr 30mA -3A Earth leakage Relay (DELAB),1nr 45kA/15kA Imax/In Type II SPD(Schneider) (Model EASY 09),1nr 30A-100A shuntcoil, 1nr Zero phase current transformer 45mm (DELAB),3nr HRC fuse holder nad 100A HRC fuse, 1nr 63A 4pole MCCB, 2nr 40A 4pole MCB, 2nr 32A 4pole MCB, 3nr 40A 2pole MCB, 3row 42way + 4pole MCCB 18kA powder coated metal enclosure box (600x800x200 mm) with cover plate 350x650x110 mm with 4nr 3phase 30A/60A Bus bar set 7 inch long.All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.(make Orange electric 10kA)MCB-Orange 10kA/Schneider	nr	1.00		
45	Supplying and fixing DB1 panel board. Including 1nr 32A 4pole MCB, 3nr 32A 2pole MCB, 3nr 40A 30mA 2pole RCCB, 15nr 6A-20A 1pole MCB, 3row 42way + 4pole MCCB 18kA powder coated metal enclosure box with cover plate 350x650x110 mm with 3nr 2A 10kA fuse MCB type, 3nr 22mm LED indicator lamp set(Chint/Andeli).All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		
46	Supplying and fixing DB2 panel board. Including 1nr 32A 4pole MCB, 3nr 32A 2pole MCB, 3nr 40A 30mA 2pole RCCB, 12nr 6A-20A 1pole MCB, 3row 42way + 4pole MCCB 18kA powder coated metal enclosure box with cover plate 350x650x110 mm with 3nr 2A 10kA fuse MCB type, 3nr 22mm LED indicator lamp set(Chint/Andeli).All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
47	Supplying and fixing DBAC panel board. Including 1nr 32A 4pole MCB, 1nr 40A 100mA 4pole RCCB, 1nr 20A 4pole MCB, 3nr 20A 1pole MCB, metal enclosure box (400x500x150 mm) with 2 phase 30A/60A bus bar set 7 inch long.All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		
48	Supplying and fixing SDBFF panel board. Including 1nr 40A 4pole MCB, 1nr 40A 100mA 4pole RCCB, 3nr 32A 2pole MCB, 2nr 32A 4pole MCB, 3row 42way + 4pole MCCB 18kA metal enclosure box (400x500x150 mm) with 2 phase 30A/60A bus bar set 7 inch longwith 3nr 2A 10kA fuse MCB type, 3nr 22mm LED indicator lamp set(Chint/Andeli).All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		
49	Supplying and fixing DB3 FF panel board. Including 1nr 32A 4pole MCB, 3nr 32A 2pole MCB, 3nr 40A 30mA 2pole RCCB, 15nr 6A-20A 1pole MCB, 3row 42way + 4pole MCCB 18kA powder coated metal enclosure box with cover plate 350x650x110 mm with 4nr 3phase 30A/60A Bus bar set 7 inch long 3nr 2A 10kA fuse MCB type, 3nr 22mm LED indicator lamp set(Chint/Andeli).All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		
50	Supplying and fixing DB2 FF panel board. Including 1nr 32A 4pole MCB, 3nr 32A 2pole MCB, 3nr 40A 30mA 2pole RCCB, 18nr 6A-20A 1pole MCB, 3row 42way + 4pole MCCB 18kA powder coated metal enclosure box with cover plate 350x650x110 mm with 3nr 2A 10kA fuse MCB type, 3nr 22mm LED indicator lamp set(Chint/Andeli).All complete as per instruction.Rate includes Copper lugs and colour caps with internal wiring.	nr	1.00		
51	Allow for testing and commissioning of the total system to the entire satisfaction of the Engineer and submission of commissioning report by chartered Electrical Engineer for 60A three phase connection	Item	1.00		
	cafeteria				
52	Supply and fixing 13Amp socket outlet with necessary PVC casing wiring (7/0.53 PVC single wire 1.5mm2) 1 core ×2, 7/0.53 earth wire (1.5mm2) all complete as per the instruction. (Socket - ACL/Chint/Krypton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Casing - Polycrome/Krypton) (Fittings - Krypton/Polycrome/Orange)	Nr	4.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
53	Supplying and fixing consumer unit 04 way surface mounted M.C.B type (incl.32 Amp. D.P MCB,40 Amp/30 mA-D.P RCCB, 4 nrs M.C.B (6 Amp.-16 Amp.)500 encloser box & bus bar fixing Philips screws (MCB - Make - Orange electric 10kA/ Schneider/Chint EB/NB7/SIMENS 5SL6 Betagard) (RCCB Make - Orange electric 10kA/Schneider/Chint NL1/SIMENS 5SV5) (Enclosure - Polycrome) Original Makes with company warranty Certificate. all complete as per instruction	Nr	1.00		
54	Supply and Fixing 12 W LED Panel light (Surface mounted/square/circuler type) Day light two years warranty with all complete as per instruction (Bulb - Orange electric ECO LED/DIMO ECO led/Green Standard) efficacy : 85 lumen / W or above	Nr	4.00		
55	Supply and Fixing concealed 1Nr point wiring (PVC) including 1/1.13 1mm2 1Cx2 wire/ gang switch/ sunk box and fixing materials. All complete as per instruction. (Switches - ACL/Chint/Krpton/Orange) (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Fittings - Krypton/Polycrome/Orange) (Conduit - Polycrome/Krypton)	Nr	4.00		
56	Supply and fixing 56" ceiling fan with fan speed controller including connecting materials (make KDK model N56RG SLS company warrenty certificate) all complete as per the instruction.	Nr	1.00		
57	Supplying & fixing 7/1.04(6mm2)(Cu/PVC/PVC) , 1 core x 2 (single phase main wire) & 7/1.04(6mm2) earth wire , incl: PVC conduit all complete as per instruction (Cable - ACL Fire Guard/Kelani/Orange/Sierra) (Conduit - Polycrome/Krypton) [Cable SLS 733]	m	55.00		
	Total carried to summary				
	PAINTING WORKS				
58	Painting walls with one coats of wall filler (internal)(after preparation of old wall)	Sq.m	2,455.00		
59	Prepare and apply approved type one coat of filler and two of emulsion paint to specified colour on sides and soffit of beams and slabs in any floor	Sq.m	1,606.00		
60	Prepare and Painting Walls with 2 coats of Emulsion paint including surface preparation of old wall.	Sq.m	2,455.00		
61	Prepare and applying Varnishing with polyurethane varnish - gloss after washing down and sand papering, 1 coat.	Sq.m	175.00		
62	Prepare and Painting steelwork, 1 coat with anticorrosive paint including removing scale and wire brushing.	Sq.m	202.00		
63	Prepare and apply Skim coat , approved type one coat of filler and two of emulsion paint to specified colour in semi rough plastered surface of sides and soffit of beams columns and slabs in any floor	Sq.m	22.00		

ID	Description	Unit	Qty.	Rate	Amount
64	Painting walls with one coats of Acrylic wall filler for external wall (after preparation of old wall) -Ground floor	Sq.m	9.10		
65	Painting walls with one coats of Acrylic wall filler for external wall (after preparation of old wall) -1st floor	Sq.m	3.50		
66	Supplying & Applying one coats of water proofing paint("Aqua shield or equivalent) for external wall- Ground floor	Sq.m	4.00		
	Total carried to summary				
	<u>ALLUMINIUM WORKS</u>				
67	Bronze anodized Partition glazed and panelled including 76X32 mm aluminium partition members and G.I. channel for frame work including 5 mm thick clear glass, 3 mm thick P.V.C. boarding rubber beading etc. Fixed partition in position as per the instructions (material available) .Rate to include for necessary screws pop rivets, rubber beadings etc. Rate includes available partition door fix in to opens as per partition drawing.	m2	288.00		
68	Supplying, fabricating & fixing Aluminium bronze anodized partition as per Drg. No. SPES/RATE23/P/01, Option 1. (Door sashes pay separately) Frame height is 2100mm. Partition panels in horizontal way should be divided in equal widths (Maximum width is 1200mm c/c). Partition frame consisting top bar (76x32mm with 70x4mm clip bar), side bars (76x32mm), horizontal middle bar (75x32mm with 70x11mm clip bar and 31x19 clip bar), bottom bar (75x32mm with 31x19 clip bar) and vertical middle bars (76x32mm with 70x11mm clip bar). If required, Squire or Circular coner bars will be paid seperately (Material cost + 20%). 4mm thick Al/PVC double side composite board for bottom panels and 5mm thick clear glass for top panels should be fixed. Rate should be included for others to manufacturer standard.	Sq.m	13.00		
69	Supplying, fabricating & fixing Aluminium bronze anodized partition paneled door as per Drg. No. SPES/RATE23/PD/01, Option 1. Frame size is 900x2070mm. Door frame around the door fixing with 18x11mm door stopper bar. Door sash consisting top bar (80x42mm), side bars (66x45mm hinges side, 70x45mm lock side), middle bar (100x42mm) and bottom bar (120x42mm). 16x15mm clip bar should be used for required bars. 4mm thick Al/PVC double side composite board for bottom panel and 5mm thick clear glass for top panel should be fixed. Rate should be included for 3 Nrs of 100x75mm Al hinges, Al bronze anodized door handle (102x40mm) pair, Door lock (CL or eq.) and others to manufacturer standard.	Sq.m	1.90		
70	Supplying 3 mm thick P.V.C. board for GI partition.	m2	72.00		
71	Supplying and fixing heavy quality Aluminium fastener (any colour). If required old accessories should be removed.	Nr	30.00		

District Engineer's (Buildings) Office - Hambanthota

ID	Description	Unit	Qty.	Rate	Amount
72	Supplying and fixing 4"x3" SS 304 hinge. If required old accessories should be removed.	Nr	20.00		
73	Supplying and fixing 14" SS 304 Bar hinge. If required old accessories should be removed.	Nr	100.00		
74	Supplying and fixing door lock (CL or equivalent approved by the Engineer). If required old accessories should be removed.	Nr	10.00		
	Total carried to summary				
	MAINTANACE WORKS				
75	Applying 2 coats of approved quality Emulsion paint to ceiling sheets & 2 coats of enamel paint to beading & moulding, including one coat of primer paint.-2nd floor	Sq.m	490.00		
	Total carried to summary				
	FORM WORK				
76	Shuttering for floor slab concrete including 15 mm plywood sheets, 4" x 2" Class (II) timber joists and necessary props, up to 12'-00" height. (Rate to include dismantling same when required). Ground floor	Sq.m	4.00		
77	Shuttering for floor slab side boards by using 1" (25mm) thick class 11 timber planks and 50x25mm timber reepers as joist at 1200mm c/c.(Rate to include for dismantling same when required) Ground floor	Sq.m	5.80		
	Total carried to summary				

District Engineer's (Buildings) Office - Hambanthota

REPAIR OF TILES AND ELECTRICAL SYSTEM IN OFFICE BUILDING AT DIVISIONAL SECRETARIAT OFFICE
THISSAMAHARAMA

Rate Schedule	Amount
(No Topic Assigned)	
PRELIMINARY WORKS	
DEMOLISH WORKS	
BRICK WORKS	
CONCRETE WORKS	
REINFORCEMENT WORKS	
PAVING WORKS	
PLASTER WORKS	
ELECTRICAL WORKS	
PAINTING WORKS	
ALLUMINIUM WORKS	
MAINTANACE WORKS	
FORM WORK	
Total	

DSH

**REPAIR OF TILES AND ELECTRICAL SYSTEM IN OFFICE BUILDING AT
DIVISIONAL SECRETARIAT OFFICE THISSAMAHARAMA**

(A) BOQ Total	:	LKR	
(B) Less for Provisional Sums	:	LKR	195,000.00
(C) Sub Total (A-B)	:	LKR	
(D) Less for Discount (If Any) (..... %)	:	LKR	
(E) Sub Total (C-D)	:	LKR	
(F) Add for Provisional Sums	:	LKR	195,000.00
Total Bid Amount (E+F) (Excluding VAT, Carried to Form of Bid))	:	LKR	=====

Total Bid Amount in Words

.....

18 % VAT : LKR

Grand Total : **LKR** _____

Note:

Bidders are requested to provide discounts, if any, as a percentage. Otherwise, it will be converted to a percentage. Your discount will also be applied to variations in quantity."

.....
Signature of Bidder